



District Water Testing Laboratory

Public Health Engineering Department,
PHE, Central Store Campus, behind Civil Police Station, Bilaspur (C.G.)
Contact as email – bspghedlab@gmail.com

Test Report

Discipline- Chemical Testing	Group- Drinking water	Report no.1185	ULR NO. :- TC1550226000001185F	
Senders name & address Mr. Jaspal Singh Math, Principal Delhi Public School Bilaspur (C.G.)	Senders letter no./Date	19.05.2026	Sampled by	Ramial Pradhan
	DL receipt no.	1185	DL Reciept date	19.05.2026
	Date of analysis started	19.05.2026	Date of analysis completed	21.05.2026

Sample Details:-

Sr. no.	Sample I.D.	District /Block	City / Village	Location/source no./GPS identification	Condition of Sample
1	05/26/1185/6868	Bilaspur	Bilaspur	Bore (Tap) Water,DPS School Bilaspur	OK
2	05/26/1185/6869	Bilaspur	Bilaspur	Filter Water,DPS School Bilaspur	OK

Details of parameters their test method units and specification as per IS/APHA :-

S.n.	Parameters	Test method IS:3025/APHA 24th ed.		Unit	As per IS-10500-2012 drinking water		Result			
		Method	Part no.		Desira ble Limit	Permi ssible Limit	1	2	3	4
1	2	3	4	5	6	7	8	9	10	11
1	Turbidity	APHA (24 th Ed)	Part-10	NTU	1	5	1.32	0.98	-	-
2	Color	APHA (24 th Ed)	Part-2120B	CU	5	15	5.0	2.0	-	-
3	Odour	IS:3025	Part-05	-	Agr	Agr	Agr	Agr	-	-
4	Taste	IS:3025	Part-05	-	Agr	Agr	-	-	-	-
5	PH @ 25°C	APHA (24 th Ed)	Part-11	PH scale	6.5-8.5	6.5-8.5	7.37	7.10	-	-
6	Total Alkalinity as CaCO ₃	APHA (24 th Ed)	Part-2320 B	mg/l.	200	600	401.3	210.4	-	-
7	TDS	APHA (24 th Ed)	Part-3550-C	mg/l.	500	2000	597	335	-	-
8	Chloride as Cl ⁻	APHA (24 th Ed)	Part-4500-Cl-B	mg/l.	250	1000	80.24	44.13	-	-
9	Total Hardness as CaCO ₃	APHA (24 th Ed)	Part-2340-C	mg/l.	200	600	430.8	229.2	-	-
10	Calcium as Ca ⁺⁺	APHA (24 th Ed)	Part-3500-Ca-B	mg/l.	75	200	99.79	53.06	-	-
11	Magnesium as Mg ⁺⁺	APHA (24 th Ed)	3500-Mg-B	mg/l.	30	100	43.63	23.24	-	-

1 The report should not be produced partly or full without approval signatory authority of legal purpose.

2 The results refer only to tested samples and parameters.

3. This Lab does not hold any responsibility for verification in results for samples kept on hold for wants of clarification.

4. Samples will be stored for a period of 10 days from date of issue of report.

5. Abbreviation Symbolize as Agr=Agreeable, Disagr=Disagreeable



Report Reviewed & Approved By

Ashish Dongre
Authorised Signatory

Annexure C

Appendix XIII

PROFORMA FOR SAFE DRINKING WATER AND SANITARY CONDITION CERTIFICATE

No. 1002/LAB/A.E./PHE/BILASPUR

Dated: 22/05/26

It is certified that an inspection team headed by Mr. Ashish Dangre, Chemist
from P.H.E. Department Bilaspur

Inspected **the DELHI PUBLIC SCHOOL RAIPUR ROAD TIFRA BILASPUR (CG)** on 19/05/26
checked the water. Test report is submitted by the school and found that the school has
potable drinking water for students and staff of the institution and is having provision for
running water in the toilets and maintaining hygienic sanitation condition in the school
building & the campus as per norms prescribed by the Centre/State/UT Government

The above certificate is valid for a period of One Year

Signature with Seal [Signature] **Chemist**
Name Mr. Ashish Dangre District Water Testing Laboratory
PHE, District Bilaspur (C.G.)
Designation Chemist

To.

**DELHI PUBLIC SCHOOL BILASPUR
RAIPUR ROAD TIFRA , BILASPUR (CG)**